



TPO M CONTROL UNIT



SKIOLD MAKES THE DIFFERENCE!

All measures in mm.

Operating Voltage	3 x 400 V + N + PE
Prefuse	Min. 10 amp.. - max. 25 amp
Alarm output	Yes
Stop System	Capacitive, 230 VAC with relay output Adjustable key distance 4-12mm Adjustable timer (delayed on release) 1 sec. - 10 min.
Stop system for hopper /flex auger	Capacitive 230 VAC with relay output Adjustable key distance 4-12mm Adjustable timer (delayed on operate) 1 sec. - 10 min.
Function	Main switch on front Start,stop and reset on front Adjustable sensor cancel time up on start Adjustable max. running time Start on 24 hour clock

Item number	Description
140601001800	Control unit TPO M 0,75kW
140601001810	Control unit TPO M 0,75kW/0,09kW
140601001820	Control unit TPO M 0,75kW/0,75kW
140601001801	Control unit TPO M 1,1kW
140601001811	Control unit TPO M 1,1kW/0,25kW
140601001821	Control unit TPO M 1,1kW/0,75kW

